



Contract

Contract Date: April 21, 2026

Project: Brecksville-Broadview Heights Middle School Grant Lighting

To: Brecksville-Broadview Heights City Schools

This contract ("Agreement") outlines the scope of work, fees, and terms and conditions associated with the project that Ameresco ("Ameresco") will complete for Brecksville-Broadview Heights City Schools ("Client"). The objective of this Agreement is to provide the Client with a turn-key solution to provide the LED Lighting upgrade at Brecksville Middle School as described in the scope of work below. **The project cost is \$597,214.00.** It is the intent of the Client to procure the goods and services through Ameresco's publicly procured, competitively solicited contract with Equalis Group. The Ameresco contract was procured by the Cooperative Council of Governments, which is a regional council of governments formed under O.R.C. Chapter 167, and is available to political subdivisions in Ohio, such as Client, under either O.R.C. § 9.48 (B)(2) generally and O.R.C. § 167.081 for certain construction and construction services purchases.

Scope of Work

LED Lighting Upgrades

Existing Conditions:

Ameresco audited more than 2,861 interior and Exterior non-LED fixtures at Brecksville-Broadview Heights Middle School. The district has completed LED lighting fixture upgrades for the auditorium and front office areas and has completed LED tube retrofits for the Gym. The remaining, non-LED lighting fixtures consist of the following technologies: 25w T8 (91%), T5 (1%), CFLs (3%), Inc (3%) and MH (2%). Existing occupancy sensors are present in some areas to help reduce runtime and consumption. Ameresco will replace all the non-LED Fixtures with LEDs.

Proposed Upgrades:

Interior Lighting- The Proposed Scope of work includes the following:

- Demo of existing surface mount strips on drop ceilings in some classrooms and hallways with new 2x2 and 2x4 LED flat panels. *(Change in Layout)*
- Demo of existing surface mount strips on structure in some classrooms with no drop ceiling with new chain hung strip 4' or 8' strip fixtures. *(Change in Layout)*
- 1 for 1 replacement of some surface mount strip and wrap fixtures on hard ceilings with new LED strip lights.
- 1 for 1 replacement of vanity fixtures for back stage with new LED fixtures.
- 1 for 1 replacement of recessed canopy, and 6" cans with new LED slim canopy and can retrofit kits.
- 2x2 recessed fixtures in hard ceiling in cafeteria hallway to be retrofitted with retrofit panel kits.
- Retrofit other linear fluorescent fixtures with 10.5w LED, direct-wired tubes. Ballasts would be eliminated with direct-wired tubes.
- Replace other existing incandescent, HID's & CFL's with equivalent LEDs.
- Cafeteria to get decorative direct/indirect LED pendants in hexagon honeycomb shape. The fixtures will be installed with wireless controls for dimming controls and scene settings with a wall mount wireless switch. Fixture clusters to be installed with occupancy sensors.
- Existing 2x2, 2x4 and 1x4 recessed acrylic lens fixtures to be retrofitted with retrofit panel kits.

Exterior Lighting- The Proposed Scope of work includes the following:

- Replace exterior non-LED fixtures with new LED fixtures.
- Add bullhorns and (2) new flood lights for 3 pole lights.
- All exterior floods and wallpacks come with integrated photocells.

Lighting models were created for areas where there are changes in lighting layouts to ensure the proposed new fixture layouts comply with OFCC OSDM School Lighting Level Recommendations.

All existing LED fixtures shall remain in place.

The proposed solution is indicative of final implementation and may be modified based on site conditions, field verification, final engineering design, any unforeseen conditions and any other code compliance issues with the existing lighting infrastructure.

All interior, exterior fixtures, and tubes will employ a uniform color temperature of 4000K to ensure consistency. Replacements for incandescent and CFL fixtures may utilize a 3500 Kelvin, depending on the specific application.

All existing fluorescent lamps containing mercury, as well as ballasts containing PCBs, will be responsibly recycled as part of this project.

The scope is turn-key and includes all labor, materials, project management, lifts, project administration, warranty, any necessary permits and drawings if dictated by the AHJ, commissioning and verification of proper operation etc. Unless otherwise noted.

A comprehensive summary of the scope, delineated by room, is included in Table 1 and Table 2 of this document.

The installation schedule is tentative and subject to the availability of the installer. However, Ameresco intends to commence work promptly and to complete as much installation activity as possible during the summer months.

Ameresco will, to the best of its ability, assist the Client in providing the documentation and paperwork necessary to satisfy reporting requirements and reimbursement requests for the State of Ohio grant that the Client was awarded on October 1, 2025.

Inclusions

- Manufacturer’s warranty will transfer to the client for lighting material. Minimum warranties are:
 - LED tubes: 5 Years
 - LED lamps: 1 Year
 - LED fixtures: 5 Years
- DDC controls warranty: 5 years on controllers
- 1 year labor warranty on lighting & lighting controls

Exclusions

Unless expressly included in the written scope of work, the following are excluded:

- DDC control integration or repair for existing lighting systems
- Excludes fixture lens or electrical repair/replacements
- Decorative, stage and auditorium lighting.
- Emergency egress lighting modification.
- LED Retrofits assumes 1:1 ballast to fixture ratio.
- Asbestos abatement
- Prevailing wages
- Taxes
- Premium time or overtime
- No provisions have been added for dust portioning, patching or painting.
- Ceiling tile replacement and install of any new 2x2 or 2x4 ceiling grids where they do not exist.

Cost Breakdown

Total Contract Value	\$597,214.00
Due at 25% project completion	\$175,000.00
Due at 50% project completion	\$140,738.00
Due at 75% project completion	\$140,738.00
Due upon project completion and Client sign-off	\$140,738.00

*** This price is only valid if executed within 30 days from the date of this Agreement. ***

Intent to Proceed

Brecksville-Broadview Heights City Schools

Ameresco, Inc.

Name: _____

Name: _____

Date: _____

Date: _____

Signature: _____

Signature: _____

Article 1 –These Terms and Conditions are incorporated into the Agreement between the Parties (collectively, the “Agreement”). Client engages Ameresco and Ameresco accepts the engagement to perform the scope of work described in this Agreement and any attachments (the “Work”). Ameresco will provide the design, procurement, construction supervision, inspection, labor, materials, tools, equipment, and other items necessary and reasonably inferable for the completion of the Work, and will substantially complete the Work by the date set forth in the Agreement (the “Contract Time”).

Article 2 - Ameresco’s Responsibilities

2.1 Ameresco will procure drawings, specifications and other documents necessary to perform the Work and will pay for and secure any and all necessary permits, fees, licenses and inspections by government agencies necessary for the Work. Client will assist in securing such permits, fees, licenses and inspections. All reports and drawings prepared for and deliverable to Client under this Agreement (“Deliverables”) become Client’s property upon full payment to Ameresco. Ameresco may retain file copies of such Deliverables. All other reports, notes, calculations, data, drawings, estimates, specifications, manuals, other documents and all computer programs, codes and computerized materials prepared by or for Ameresco (“Instruments”) remain Ameresco’s property. Upon execution of this Agreement, Ameresco grants Client a non-exclusive license to retain, use and make copies, of Ameresco’s Instruments in connection with the Client’s use and occupancy of the Project, provided that the Client has paid to Ameresco all amounts due and payable as of the date of Ameresco’s cessation of performance.

2.2 Ameresco is not responsible for the maintenance, repair or replacement of non-maintainable, non-replaceable, or obsolete parts of equipment already existing at the Facilities. Unless expressly agreed in writing, Ameresco is not responsible for the removal or reinstallation of replacement valves, dampers, or waterflow and tamper switches with respect to pipes and ductwork, including vent or drain system. Ameresco assumes no responsibility for any service performed on any equipment other than by Ameresco or its agents.

2.3 At its option, Ameresco may subcontract some or all of the Work or Services, but no contractual relationship will exist between Client and any subcontractor. Ameresco is responsible for the management of its subcontractors in their performance of their work.

Article 3 - Client’s Responsibilities

3.1 Client, without cost to Ameresco, shall **(a)** provide or arrange for, upon reasonable notice, access and make all reasonable provisions for Ameresco to enter any site where Work is to be performed (the “Site”); **(b)** permit Ameresco to control and operate all building controls, systems, apparatus, equipment and machinery necessary to perform the Work; **(c)** furnish Ameresco with blueprints, surveys, legal descriptions, waste management plans and all other information pertinent to the Work and any Site where the Work is to be performed that are known to be existing and available to Client; **(d)** cooperate with Ameresco in obtaining permits and consents from government authorities and others as may be required by Ameresco for performance of the Work so as not to affect the timelines set forth in this Agreement; **(e)** notify Ameresco promptly of all known or suspected hazardous materials, asbestos or mold at the Site and any other conditions requiring special care; **(f)** provide Ameresco with legally required materials and information (including but not limited to Material Safety Data Sheets) related to all hazardous materials located at any Site where the Work is to be performed; **(g)** furnish Ameresco with any contingency plans, safety programs and other policies, plans or programs related to any Site where the Work is to be performed; **(h)** operate, service and maintain all equipment according to the manufacturer’s recommendations including those set forth in the manufacturer’s operating manuals or instructions, as well as all requirements of applicable law or of authorities having jurisdiction; and **(i)** promptly notify Ameresco of all unusual or materially changed operating conditions, hours of usage, system malfunctions, installed equipment or building alterations that may affect the equipment or energy usage or any Services.

3.2 Client acknowledges that the technical and pricing information contained in this Agreement is confidential and proprietary to Ameresco and agrees not to disclose it or otherwise make it available to others without Ameresco’s express written consent. This imposes no obligation upon Client with respect to confidential information that: (a) the Client can demonstrate was already in the Client’s actual possession or knowledge and which Client lawfully acquired other than from Ameresco was; (b) is or becomes publicly available through no fault, action, omission or intervention of Client; (c) is received by Client from a third party without a duty of confidentiality (express or implied) owed to Ameresco; (d) is independently developed by Client without a breach of this Agreement; (e) is disclosed by Client with the Ameresco’s prior written approval; or (f) is required to be disclosed by operation of law, court order or other governmental demand.

Article 4 - Changes and Delays

4.1 As the Work is performed, conditions may change or circumstances outside Ameresco’s reasonable control (including changes of law) may develop which would require Ameresco to expend additional costs, effort or time to complete the Work, in which case Ameresco will submit a request for Client’s approval for an equitable adjustment in the Contract Price, the Contract Time, or in both.

4.2 If conditions are encountered at the jobsite that are (1) subsurface or otherwise concealed physical conditions which differ materially from those indicated in the Agreement, or (2) unknown physical conditions of an unusual nature, which differ materially from those ordinarily found to exist and generally recognized as inherent in construction activities of the character provided for in this Agreement, then written notice by Ameresco shall be given to Client promptly before conditions are disturbed and in no event later than 21 days after first observance of the conditions. If requested, an equitable adjustment to Contract Price and Contract Time shall be made by a change order. If agreement cannot be reached by the Parties within 10 days, Ameresco may assert a claim for an equitable adjustment in the Contract Price or Contract Time or both. Failure to properly submit written notice of such conditions within the time required represents an irrevocable waiver of Ameresco’s right to assert a claim for an increase in the Contract Price or Contract Time.

4.3 Ameresco shall not be responsible for loss, delay, injury, damage or failure of performance that may be caused by circumstances beyond its control, including but not restricted to acts or omissions by Client or its employees, agents or contractors, Acts of God, war, civil commotion, acts or omissions of government authorities, fire, theft, corrosion, flood, water damage, lightning, freeze-ups, strikes, lockouts, differences with workmen, riots, explosions, quarantine restrictions, delays in transportation, or shortage of vehicles, fuel, labor or materials. In the event of such delay or failure, the time for performance shall be extended by a period equal to the time lost plus a reasonable recovery period and the compensation shall be equitably adjusted for additional costs Ameresco incurs due to such delay.

Article 5 – Compensation

5.1 Client shall pay Ameresco the Contract Price on a monthly basis based on percent complete within 30 days of Client’s receipt of Ameresco’s invoice. Payments shall be made on account of materials and equipment delivered and suitably stored at the Site for subsequent incorporation in the Work. Off-Site storage of materials is permitted. Upon final completion of the Work, Ameresco shall submit to Client a final invoice of all remaining sums. Payment of the final payment shall be made within 30 days after Client’s receipt of the final Application for Payment.

5.2 Except to the extent expressly agreed in writing, Ameresco’s fees do not include any taxes, excises, fees, duties, tariffs or other government charges related to the Work, and Client shall pay such amounts or reimburse Ameresco for any amounts it pays. If Client claims a tax exemption or direct payment permit, it shall provide Ameresco with a valid exemption certificate or permit.

Article 6 – Insurance, Indemnification, and Limitation of Liability

6.1 By Ameresco: Ameresco shall maintain at its expense: (i) Workers’ Compensation and Employer’s Liability Insurance as required by applicable State law; (ii) Commercial General Liability Insurance (including contractual liability) with limits of \$1 million per person/occurrence for bodily injury, property damage, and personal injury; and (iii) Comprehensive Automobile Liability Insurance (owned, non-owned, and hired) with limits of \$1 million per person/occurrence. Ameresco

shall provide Client a Certificate of Insurance naming Client as an additional insured under (ii) and (iii).

6.2 Risk of loss of materials and Equipment furnished by Ameresco shall pass to Client upon delivery to Client's premises, and Client shall be responsible for protecting and insuring them against theft and damage.

6.3 ANYTHING HEREIN NOTWITHSTANDING, IN NO EVENT SHALL AMERESCO BE RESPONSIBLE UNDER THIS AGREEMENT FOR INCIDENTAL, CONSEQUENTIAL, PUNITIVE, EXEMPLARY OR SPECIAL DAMAGES, INCLUDING WITHOUT LIMITATION LOST PROFITS, LOSS OF USE AND/OR LOST BUSINESS OPPORTUNITIES, WHETHER ARISING IN WARRANTY, LATE OR NON-DELIVERY OF ANY WORK, TORT, CONTRACT OR STRICT LIABILITY, AND REGARDLESS OF WHETHER CUSTOMER HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGES AND, IN ANY EVENT, AMERESCO'S AGGREGATE LIABILITY FOR ANY AND ALL CLAIMS, LOSSES OR EXPENSES (INCLUDING ATTORNEYS FEES) ARISING OUT OF THIS AGREEMENT, OR OUT OF ANY WORK FURNISHED UNDER THIS AGREEMENT, WHETHER BASED IN CONTRACT, NEGLIGENCE, STRICT LIABILITY, AGENCY, WARRANTY, TRESPASS, INDEMNITY OR ANY OTHER THEORY OF LIABILITY, SHALL BE LIMITED TO \$1,000,000. AMERESCO reserves the right to control the defense and settlement of any claim for which Ameresco has an obligation to indemnify hereunder. The parties acknowledge that the price which Ameresco has agreed to perform its Work and obligations under this Agreement is calculated based upon the foregoing limitations of liability, and that Ameresco has expressly relied on, and would not have entered into this Agreement but for such limitations of liability.

6.4 Ameresco (the "Indemnifying Party") shall indemnify, defend, and hold harmless the Client and its officers, agents, and employees from and against any and all third-party claims, damages, losses, or expenses arising out of or resulting from the Indemnifying Party's negligence or willful misconduct, but only to the extent such claims are not caused by the negligence or willful misconduct of the other Party. Ameresco's indemnity obligations are limited to the proceeds of its applicable Commercial General Liability Insurance policy.

Article 7 - Hazardous Material Provisions

7.1 The Work does not include directly or indirectly performing or arranging for the detection, monitoring, handling, storage, removal, transportation, disposal or treatment of Oil or Hazardous Materials. Except as disclosed pursuant to Section 7.3, Client represents that there is no asbestos or any other hazardous or toxic materials, as defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, as amended, the regulations promulgated thereunder, and other applicable federal, state or local law ("Hazardous Materials"), present at Client's locations where Work is performed. Ameresco will notify Client immediately if it discovers or suspects the presence of any Hazardous Material. All Work has been priced and agreed to by Ameresco in reliance on Client's representations as set forth in this Section 7.1. The presence of Hazardous Materials constitutes a change in the Proposed Solution equivalent to a change order whose terms must be agreed to by Ameresco before its obligations hereunder will continue.

7.2 Client shall be solely responsible for testing, abating, encapsulating, removing, remedying or neutralizing such Hazardous Materials, and for the costs thereof. Even if an appropriate change order has been entered into pursuant to Section 7.1 above, Ameresco will continue to have the right to stop the Work until the job site is free from Hazardous Materials. In such event, Ameresco will receive an equitable extension of time to complete its Work, and compensation for delays caused by Hazardous Materials remediation. In no event shall Ameresco be required or construed to take title, ownership or responsibility for such Oil or Hazardous Materials. Client shall sign any required waste manifests in conformance with all government regulations, listing Client as the generator of the waste.

7.3 Client warrants that, prior to the execution of the Agreement, it has notified Ameresco in writing of any and all Hazardous Materials present, potentially present or likely to become present at Client's locations and has provided a copy of any jobsite safety policies, including but not limited to lock-out and tag procedures, laboratory procedures, chemical hygiene plan, material safety

Article 8 – Warranty

8.1 Client shall have good and clear title to all equipment and material furnished to Client pursuant to this Agreement (except licensed software, which shall be governed exclusively by the terms and conditions of the Software License Agreement), free and clear of liens and encumbrances.

8.2 Ameresco warrants the Work, materials, and equipment against defects in materials and workmanship for one (1) year from the date of Substantial Completion of the applicable Work. Ameresco shall assign to Client any and all manufacturers and/or installer's warranties for equipment or material provided as part of the Work, to the extent that such third-party warranties are assignable.

8.3 The warranties and guarantees set forth in this Agreement will be void as to, and shall not apply to, any Equipment (i) improperly repaired, altered or installed except when such improper repair, alteration or installation is performed by Ameresco or its authorized representatives and Subcontractor; (ii) subjected to unreasonable or improper use or storage, used beyond rated conditions, operated other than per Ameresco's or the manufacturer's instructions, or otherwise subjected to improper maintenance, negligence or accident; (iii) damaged because of any use of the Equipment after Client has, or should have, knowledge of any defect in the Equipment. Ameresco assigns to Client, without recourse, any and all assignable warranties available from any manufacturer, supplier, or Subcontractor of such Equipment.

8.4 Any claim under the warranty granted in this Agreement must be made per the terms of this Agreement. Such warranty only extends to Client and not to any subsequent owner of the Equipment.

8.5 It is understood and agreed that the warranties and guarantees as provided in this Agreement are the sole warranties and guarantees provided by Ameresco and are given in lieu of any other express or implied warranties, including any and all warranties that are not provided by Ameresco in this Agreement.

Article 9 - Miscellaneous Provisions

9.1 Notices between the parties shall be in writing and shall be sent by overnight carrier or acknowledged email to the other party.

9.2 This Agreement shall be governed by the laws of the state the Project is located in, and the parties agree to the exclusive jurisdiction of any state or federal court located in such state.

9.3 A party's waiver of any breach of this Agreement does not waive any subsequent breach. All waivers must be in writing signed by the party to be bound.

9.4 This Agreement constitutes the complete agreement between the parties and supersedes all prior and contemporaneous negotiations, representations, agreements, awards, or proposals, either written or oral, relative to the same. Only a written instrument signed by both parties may modify this Agreement.

9.5 Any dispute arising out of or related to this Agreement ("Dispute") shall first be submitted to the Parties' respective project representatives for resolution. If unresolved, senior management of both Parties shall meet within ten (10) business days to attempt resolution. If the Dispute remains unresolved after thirty (30) days from that meeting, either Party may submit it to mediation. Mediation fees shall be shared equally and held at the Project location, unless otherwise agreed. Any agreement reached in mediation shall be enforceable as a settlement agreement. If mediation fails, either Party may pursue any available remedy at law or in equity.

Article 10 – Termination. If Client fails to make payments as they become due, or otherwise defaults or breaches its obligations under this Agreement, Ameresco may give written notice to Client of Ameresco's intention to suspend or terminate this Agreement. If, within 15 days following receipt of such notice, Client fails to make payments then due, or otherwise fails to cure or perform its obligations, Ameresco may, by written notice to Client, immediately terminate this Agreement and recover from Client payment for Work executed.

Table 1

BBHCSD MS- LED LIGHTING- EXTERIOR LIGHTING SOLUTIONS

Item #	Location	Tech	Mount	Existing Fixture Code	Qty	Input Watts	Solution	New Fixture (OR Equal)	Qty	Input Watts
1	Door 20	Inc	Recessed	50w inc Round Recessed Canopy 8"	2	50	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	2	22
2	Door 20 wall	MH	Surface	150 MH Trad Wallpack	1	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	1	65
3	Door 20 Wall 2	MH	Surface	150 MH Trad Wallpack	1	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	1	65
4	Door 19	Inc	Surface	50w inc Door Entry Light	1	50	New Fixture	LED VANCE MWLPAKN2AS030UNHDSC2BZP 10/CS 1/SKU 20w setting	1	20
5	Door 16	Inc	Recessed	50w inc Round Recessed Canopy 8"	1	50	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	1	22
6	Door 15 wall	MH	Surface	150 MH Trad Wallpack	1	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	1	65
7	Door 24 Wall	MH	Surface	250w MH Trad Wallpack	1	295	New Fixture	LED VANCE WALPAKN9AS080UNHD8SC2BZP 80w Setting	1	80
8	Door 25 Wall	MH	Surface	150 MH Trad Wallpack	1	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	1	65
9	Door 25	Inc	Recessed	50w inc Round Recessed Canopy 8"	1	50	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	1	22
10	Door 13 Wall	MH	Surface	150 MH Trad Wallpack	1	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	1	65
11	Door 9 Wall	MH	Surface	150 MH Trad Wallpack	1	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	1	65
12	Door 7	Inc	Recessed	50w inc Round Recessed Canopy 8"	2	50	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	2	22
13	East Side Windows	LED	Recessed	6" Cans above Windows- LED Screw ins	28	15	Existing			
14	Door 6 Roof	MH	Surface	250w MH Flood Light- Trunion	1	295	New Fixture	LED VANCE FLOODLTPS140UNHD8SC2ADJBZP 140w setting	1	140
15	Door 6	Inc	Recessed	50w inc Round Recessed Canopy 8"	1	50	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	1	22
16	Door 5	Inc	Recessed	12x12 Square Canopy Recessed-100w inc	8	100	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	8	22
17	Door 4- Flag Light	MH	Slip Fit	150w MH Focused Flag Flood Light- Aim at Flag SlipFitter	1	190	New Fixture	LED VANCE FLOODLTPS140UNHD8SC2ADJBZP 100w Setting	1	100
18	Door 4	Inc	Recessed	12x12 Square Canopy Recessed-100w inc	9	100	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	9	22
19	Door 3 Wall	LED	Surface	LED Wallpack 50w?	1	50	Existing			
20	Door 2 Wall	LED	Surface	LED Wallpack 50w?	1	50	Existing			
21	Door 1	Inc	Recessed	50w inc Round Recessed Canopy 8"	2	50	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	2	22
22	CR 200 L Wall	MH	Surface	150 MH Trad Wallpack	1	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	1	65
23	Security Notice Wall	MH	Surface	150 MH Trad Wallpack	1	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	1	65
24	Door 35	Inc	Recessed	50w inc Round Recessed Canopy 8"	2	50	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	2	22
25	Door 35 Wall	MH	Surface	150 MH Trad Wallpack	1	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	1	65
26	Door 34 Wall	MH	Surface	150 MH Trad Wallpack	2	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	2	65
27	Door 34	Inc	Recessed	50w inc Round Recessed Canopy 8"	4	50	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	4	22
28	CR 207 Wall	MH	Surface	150 MH Trad Wallpack	1	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	1	65
29	CR 212 Wall	MH	Surface	150 MH Trad Wallpack	2	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	2	65
30	Door 33	Inc	Recessed	50w inc Round Recessed Canopy 8"	2	50	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	2	22
31	Door 31/32	Inc	Recessed	100w inc? SM Square Canopy-12x12"	2	100	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	2	22
32	Small Wall next	MH	Surface	150 MH Trad Wallpack	1	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	1	65
33	Door 30	Inc	Recessed	50w inc Round Recessed Canopy 8"	2	50	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	2	22
34	Door 30 wall	MH	Surface	150 MH Trad Wallpack	1	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	1	65
35	Door 28 Wall	MH	Surface	250w MH Trad Wallpack	2	295	New Fixture	LED VANCE WALPAKN9AS080UNHD8SC2BZP 80w Setting	2	80
36	Door 27	Inc	Recessed	50w inc Round Recessed Canopy 8"	2	50	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	2	22
37	Door 27A Wall	MH	Surface	150 MH Trad Wallpack	1	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	1	65
38	TLC Wall	MH	Surface	150 MH Trad Wallpack	4	190	New Fixture	LEDVANCE WALPAKN9AS080UNHD8SC2BZP 65w setting	4	65
39	Door 26	Inc	Recessed	50w inc Round Recessed Canopy 8"	1	50	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	1	22
40	South Parking Lot	MH	Slip Fit	400w MH Drum Flood Light	1	458	New Fixture	(2) FLOODLTPS140UNHD8SC2ADJBZP + (1) POLESQS2CDBLBULHORNHBZ 1/CS 1/SKU+ (2) FLOODLTPSYOKE140WBZ- 140w setting	1	280
40	South Parking Lot	MH	Trunion	400w MH Trad Flood Light Trunion	1	458	New Fixture	(2) FLOODLTPS140UNHD8SC2ADJBZP + (1) POLESQS2CDBLBULHORNHBZ 1/CS 1/SKU+ (2) FLOODLTPSYOKE140WBZ-140w setting	1	280
41	North Parking Lot	MH	Slip Fit	400w MH Drum Flood Light	1	458	New Fixture	(2) FLOODLTPS140UNHD8SC2ADJBZP + (1) POLESQS2CDBLBULHORNHBZ 1/CS 1/SKU+ (2) FLOODLTPSYOKE140WBZ- 140w setting	1	280
End	End	End	End	End	End	End	End	End	End	End

Table 2

BBHCSD MS- LED LIGHTING- INTERIOR LIGHTING SOLUTIONS

Rm #	Room	Tech	Mount	Fixture Code	Qty	Input Watts	Solution	New Fixture Code	Qty	Input Watts
1	MAINTANCE OFFICE	FL	Surface	2L-F48-T8-25w	6	44	Retrofit	2L-F48-T8-10.5w LED	6	21
2	CR #125	FL	Surface	2L-F48-T8-25w	24	44	Remove	Demo Existing Fixture	24	0
2	CR #125	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
3	CR #124	CFL	Suspended	2L-13w CFL Screw in- red color bulb	1	26	Existing			
3	CR #124	LED	Suspended	New 40w LED Suspended 4' Strip Fixture	13	0	New Fixture	New 40w 4' LED Chain Hung Strip w/ Light Model Layout	13	40
3	CR #124	FL	Surface	2L-F48-T8-25w	44	44	Remove	Demo Existing Fixture	44	0
4	STORAGE 124 c	FL	Surface	2L-F48-T8-25w	6	44	Retrofit	2L-F48-T8-10.5w LED	6	21
4	STORAGE 124 c	FL	[INTERIOR]	1L-F48-T8-25w	4	22	Retrofit	1L-F48-T8-10.5w LED	4	11
4	STORAGE 124 c	FL	[INTERIOR]	2L-F48-T8-25w	6	44	Retrofit	2L-F48-T8-10.5w LED	6	21
5	ROOM 124A LOUNGE	LED	Recessed	New 2x4 40w LED Flat Panel	3	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	3	40
5	ROOM 124A LOUNGE	FL	Surface	2L-F48-T8-25w	6	44	Remove	Demo Existing Fixture	6	0
6	CR #123	FL	Surface	2L-F48-T8-25w	1	44	New Fixture	20w 4' LED SM Strip	1	20
6	CR #123	LED	Suspended	New 40w LED Suspended 4' Strip Fixture	6	0	New Fixture	New 40w 4' LED Chain Hung Strip w/ Light Model Layout	6	40
6	CR #123	FL	Surface	2L-F48-T8-25w	26	44	Remove	Demo Existing Fixture	26	0
7	STORAGE 123A	FL	Surface	2L-F48-T8-25w	20	44	Retrofit	2L-F48-T8-10.5w LED	20	21
7	STORAGE 123A	FL	[INTERIOR]	1L-F48-T8-25w	7	22	Retrofit	1L-F48-T8-10.5w LED	7	11
7	STORAGE 123A	CFL	[INTERIOR]	1L-26w CFL screw in A19	3	26	Retrofit	1L-15w LED screw in	3	15
8	STORAGE 124B	FL	Surface	2L-F48-T12-34w	2	72	Retrofit	1L-F48-T8-10.5w LED w/ TS	2	11
9	CR #122	FL	Surface	2L-F48-T8-25w	18	44	Remove	Demo Existing Fixture	18	0
9	CR #122	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
10	TEACHER OFFICE 122A	FL	[INTERIOR]	1L-F48-T8-25w	3	22	Retrofit	1L-F48-T8-10.5w LED	3	11
11	CR #121	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
11	CR #121	FL	Surface	2L-F48-T8-25w	18	44	Remove	Demo Existing Fixture	18	0
12	CR #120	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
12	CR #120	FL	Surface	2L-F48-T8-25w	18	44	Remove	Demo Existing Fixture	18	0
13	MUSIC CR #119	LED	Surface	New 20w 4' LED SM Strip	77	0	New Fixture	New 20w 4' LED SM Strip (1 for 1 replacement)	77	20
13	MUSIC CR #119	FL	Surface	2L-F48-T8-25w	77	44	Remove	Demo Existing Fixture	77	0
14	MUSIC STORAGE 119B	FL	Surface	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
15	MUSIC STORAGE 119C	FL	Surface	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
16	OFFICE -119A	FL	Surface	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
17	PARC ROOM HALLWAY	FL	Surface	2L-F48-T8-25w	10	44	Retrofit	2L-F48-T8-10.5w LED	10	21
18	IT OFFICE 126	FL	Surface	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
19	OFFICE 127	FL	Surface	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
20	OFFICE 128	FL	Surface	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
21	PRAC 130	FL	Surface	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
22	PARC 129	LED	Recessed	LED 2x2 FPs 30w	5	30	Existing			
23	PARC 131	FL	Surface	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
24	PARC 132	FL	Surface	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
25	PARC 133	FL	Surface	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
26	PARC 134	FL	Surface	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
27	PARC 135	FL	Surface	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
28	BACK STAGE AREA	LED	Suspended	1L-A19-15w LED Screw in	12	15	Retrofit	1L-25w LED Corn Cob	12	25
29	BACK STAGE VARIETY AREA	FL	Surface	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
29	BACK STAGE VARIETY AREA	Inc	Surface	4L-50w inc Makeup Vanity Globe Bulbs	9	200	New Fixture	24w LED Vanity Light Bar	9	24
30	BACK STAGE AREA 136A	FL	[INTERIOR]	1L-F48-T8-25w	4	22	Retrofit	1L-F48-T8-10.5w LED	4	11

Table 2 continued on next page

Table 2 Continued

31	STAGE STORAGE 137	FL	Surface	2L-F48-T8-25w	5	44	Retrofit	2L-F48-T8-10.5w LED	5	21
32	CR #117	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
32	CR #117	FL	Surface	2L-F48-T8-25w	18	44	Remove	Demo Existing Fixture	18	0
33	AUDI STORAGE 149	FL	Surface	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED	1	21
33	AUDI STORAGE 149	FL	Surface	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED	1	21
34	AUDI STORAGE 146	FL	Surface	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED	1	21
35	AUDI STORAGE 145	FL	Surface	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED	1	21
36	AUDI STORAGE 142	FL	Surface	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED	1	21
37	HALLWAY OUTSIDE CR 117	FL	Recessed	2L-F48-T8-25w	8	44	New Fixture	2x4 LED Hinge Panel 30w	8	30
38	BOYS RR 117A	FL	Recessed	4L-F48-T8-25w	6	85	New Fixture	2x4 LED Hinge Panel 30w	6	30
39	117B CUST CLOSET	FL	[INTERIOR]	1L-F48-T8-25w	1	22	Retrofit	1L-F48-T8-10.5w LED	1	11
40	GIRLS RR117C	FL	Surface	1L-F48-T8-25w	9	22	Remove	Demo Existing Fixture	9	0
40	GIRLS RR117C	LED	Recessed	New 2x4 40w LED Flat Panel	6	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	6	40
41	HALLWAY DOOR 6	FL	Recessed	2L-F48-T8-25w	2	44	New Fixture	2x4 LED Hinge Panel 30w	2	30
42	STORAGE 117D	CFL	[INTERIOR]	1L-26w CFL screw in A19	1	26	Retrofit	1L-15w LED screw in	1	15
43	HALLWAY 117D	FL	Recessed	2L-F48-T8-25w	4	44	New Fixture	2x4 LED Hinge Panel 30w	4	30
44	HALLWAY OUTSIDE CR 116	FL	Recessed	2L-F48-T8-25w	14	44	New Fixture	2x4 LED Hinge Panel 30w	14	30
45	CR #116	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
45	CR #116	FL	Surface	2L-F48-T8-25w	18	44	Remove	Demo Existing Fixture	18	0
46	MUSIC #138	LED	Surface	New 20w 4' LED SM Strip	50	0	New Fixture	New 20w 4' LED SM Strip (1 for 1 replacement)	50	20
46	MUSIC #138	FL	Surface	2L-F48-T8-25w	50	44	Remove	Demo Existing Fixture	50	0
47	MUSIC STORAGE	FL	Surface	2L-F48-T8-25w	5	44	Retrofit	2L-F48-T8-10.5w LED	5	21
48	CR #115	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
48	CR #115	FL	Surface	2L-F48-T8-25w	18	44	Remove	Demo Existing Fixture	18	0
49	CR #114	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
49	CR #114	FL	Surface	2L-F48-T8-25w	18	44	Remove	Demo Existing Fixture	18	0
50	CR #113	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
50	CR #113	FL	Surface	2L-F48-T8-25w	18	44	Remove	Demo Existing Fixture	18	0
51	CR #112	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
51	CR #112	FL	Surface	2L-F48-T8-25w	18	44	Remove	Demo Existing Fixture	18	0
52	COPY ROOM 150	FL	Surface	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
53	STAGE	CFL	[INTERIOR]	1L-26w CFL screw in A19	15	26	Retrofit	1L-15w LED screw in	15	15
54	DOOR #5 HALLWAY	MH	[INTERIOR]	1L-50w MH	8	72	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	8	22
55	DOOR #5 VESTIBULE	MH	[INTERIOR]	1L-50w MH	4	72	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	4	22
56	MAIN AUDITORIUM HALLWAY	FL	Recessed	4L-F48-T8-25w	22	85	New Fixture	2x4 LED Hinge Panel 30w	22	30
57	AUDI DOOR #1	MH	[INTERIOR]	1L-50w MH	4	72	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	4	22
58	AUDI DOOR #2	MH	[INTERIOR]	1L-50w MH	4	72	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	4	22
59	AUDI DOOR #3	MH	[INTERIOR]	1L-50w MH	4	72	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	4	22
60	AUDI DOOR #4	MH	[INTERIOR]	1L-50w MH	4	72	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	4	22
61	HALL SEATING AREA	MH	[INTERIOR]	1L-50w MH	3	72	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	3	22
62	DOOR #4 VESTIBULE	MH	[INTERIOR]	1L-50w MH	6	72	New Fixture	Liton LCMPD12Q-W-TS40-22w 4000k	6	22
63	HALL OUTSIDE CR #111	FL	Recessed	2L-F48-T8-25w	1	44	New Fixture	2x4 LED Hinge Panel 30w	1	30
64	CR #111	LED	Recessed	New 2x4 40w LED Flat Panel	12	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	12	40
64	CR #111	FL	Surface	2L-F48-T8-25w	24	44	Remove	Demo Existing Fixture	24	0
65	CR #109	FL	Recessed	3L-F48-T8-25w	9	66	New Fixture	2x4 LED Hinge Panel 30w	9	30
66	STORAGE 109A	FL	[INTERIOR]	1L-F48-T8-25w	2	22	Retrofit	1L-F48-T8-10.5w LED	2	11
67	STAFF WRR	FL	Surface	2L-F48-T8-25w	8	44	Retrofit	2L-F48-T8-10.5w LED	8	21
68	SHOW CASE	FL	[INTERIOR]	1L-F48-T8-25w	4	22	Retrofit	1L-F48-T8-10.5w LED	4	11
69	HALLWAY RAMP	FL	Recessed	3L-F48-T8-25w	8	66	New Fixture	2x4 LED Hinge Panel 30w	8	30
70	STORAGE 143	FL	Surface	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21

Table 2 continued on next page

Table 2 Continued

71	HALLWAY NEXT AUDIT	FL	Recessed	2L-F48-T8-25w	15	44	New Fixture	2x4 LED Hinge Panel 30w	15	30
72	HALLWAY DOOR #17	FL	Recessed	2L-F48-T8-25w	1	44	New Fixture	2x4 LED Hinge Panel 30w	1	30
73	MECH HALLWAY 137	CFL	[INTERIOR]	1L-26w CFL screw in A19	1	26	Retrofit	1L-15w LED screw in	1	15
73	MECH HALLWAY 137	FL	Suspended	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED	1	21
74	BOILER ROOM	FL	Suspended	2L-F48-T8-25w	8	44	Retrofit	2L-F48-T8-10.5w LED	8	21
75	ELECTRICAL ROOM	FL	Suspended	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
76	CAFETERIA SECTION #1	FL	Surface	2L-F48-T8-25w	126	44	Remove	Demo Existing Fixture	126	0
76	CAFETERIA SECTION #1	LED	Suspended	New 8' and 4' Honeycomb Shape LEDs	6	0	New Fixture	(6F) 8' 40w LED Decorative Linear Pendant w/ Light Model Layout and Wireless Controls	6	240
76	CAFETERIA SECTION #1	LED	Suspended	New 4' Honeycomb Shape LEDs	2	0	New Fixture	(6F) 4' 20w LED Decorative Linear Pendant w/ Light Model Layout and Wireless Controls	2	120
77	CAFETERIA SECTION #2	FL	Surface	2L-F48-T8-25w	126	44	Remove	Demo Existing Fixture	126	0
77	CAFETERIA SECTION #2	LED	Suspended	New 8' and 4' Honeycomb Shape LEDs	6	0	New Fixture	(6F) 8' 40w LED Decorative Linear Pendant w/ Light Model Layout and Wireless Controls	6	240
77	CAFETERIA SECTION #2	LED	Suspended	New 4' Honeycomb Shape LEDs	2	0	New Fixture	(6F) 4' 20w LED Decorative Linear Pendant w/ Light Model Layout and Wireless Controls	2	120
78	SERVING AREA	FL	Surface	1L-F48-T8-25w	56	22	Remove	Demo Existing Fixture	56	0
78	SERVING AREA	LED	Recessed	New 2x4 40w LED Flat Panel	20	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	20	40
79	LAUNDRY	FL	[INTERIOR]	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED	1	21
80	KITCHEN	FL	Surface	2L-F48-T8-25w	39	44	Retrofit	2L-F48-T8-10.5w LED	39	21
81	KITCHEN STORAGE	FL	Surface	2L-F48-T8-25w	10	44	Retrofit	2L-F48-T8-10.5w LED	10	21
82	KITCHEN OFFICE	FL	Surface	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
83	KITCHEN RECEIVING	FL	Surface	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
84	HOOD #1	CFL	[INTERIOR]	1L-26w CFL screw in A19	10	26	Retrofit	1L-15w LED screw in	10	15
85	HOOD #2	CFL	[INTERIOR]	1L-26w CFL screw in A19	5	26	Retrofit	1L-15w LED screw in	5	15
86	STAFF CAFETERIA	LED	Recessed	New 2x4 40w LED Flat Panel	10	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	10	40
86	STAFF CAFETERIA	FL	Surface	2L-F48-T8-25w	25	44	Remove	Demo Existing Fixture	25	0
87	COOLER	CFL	[INTERIOR]	1L-26w CFL screw in A19	3	26	Retrofit	1L-15w LED screw in	3	15
88	LOCKER ROOM 243C	FL	Surface	2L-F48-T8-25w	3	44	Retrofit	2L-F48-T8-10.5w LED	3	21
89	STAFF RR 243D	Inc	Surface	2L-100w inc	1	200	Retrofit	2L-15w LED screw in A19	1	30
90	DISHWASHING	FL	Surface	2L-F48-T8-25w	6	44	Retrofit	2L-F48-T8-10.5w LED	6	21
91	243N JAN CLOSET	FL	[INTERIOR]	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED	1	21
92	HALLWAY OUTSIDE CAFETERIA	FL	Recessed	2L-F24-T8U-25w	7	44	New Fixture	2x2 LED Hinge Panel 20w	7	20
92	HALLWAY OUTSIDE CAFETERIA	FL	Surface	2L-F24-T8U-25w	2	44	New Fixture	2x2 LED Hinge Panel 20w	2	20
93	SHOW CASE	CFL	[INTERIOR]	6" Can 26w CFL screw in	4	26	New Fixture	6" LED Can Retrofit 12w	4	12
94	245 JAN CLOSET	CFL	[INTERIOR]	1L-26w CFL screw in A19	2	26	Retrofit	1L-15w LED screw in	2	15
95	246 MENS STAFF RR	CFL	[INTERIOR]	1L-26w CFL screw in A19	1	26	Retrofit	1L-15w LED screw in	1	15
95	246 MENS STAFF RR	FL	Surface	2L-F24-T8U-25w	1	44	New Fixture	2x2 LED Hinge Panel 20w	1	20
96	BOILER ROOM HALLWAY	FL	Surface	1L-F48-T8-25w	16	22	New Fixture	20w 4' LED SM Strip	16	20
97	247 BOILER ROOM	FL	Suspended	2L-F48-T8-25w	5	44	Retrofit	2L-F48-T8-10.5w LED	5	21
98	DOOR #24 HALLWAY	FL	Surface	1L-F48-T8-25w	9	22	Remove	Demo Existing Fixture	9	0
98	DOOR #24 HALLWAY	LED	Recessed	New 2x2 30w LED Flat Panel	3	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	3	30
99	CLOSET 249	CFL	[INTERIOR]	1L-26w CFL screw in A19	1	26	Retrofit	1L-15w LED screw in	1	15
100	2ND FLOOR STAIRS	FL	Surface	2L-F48-T8-25w	5	44	New Fixture	20w 4' LED SM Strip	5	20
101	HALLWAY OUTSIDE TLC	FL	Recessed	3L-F48-T8-25w	3	66	New Fixture	2x4 LED Hinge Panel 30w	3	30
102	MS GYM	FL	Suspended	4L-F48-T5 HO-49w	32	211	Existing			
103	HALLWAY OUTSIDE GYM	FL	Recessed	3L-F48-T8-25w	4	66	New Fixture	2x4 LED Hinge Panel 30w	4	30
104	STORAGE ROOM 251	FL	[INTERIOR]	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
105	STORAGE ROOM 252	CFL	[INTERIOR]	1L-26w CFL screw in A19	2	26	Retrofit	1L-15w LED screw in	2	15
106	STORAGE ROOM 252A	CFL	[INTERIOR]	1L-26w CFL screw in A19	2	26	Retrofit	1L-15w LED screw in	2	15
107	TLC STAIR	FL	Surface	2L-F48-T8-25w	1	44	New Fixture	20w 4' LED SM Strip	1	20
108	DOOR 25	FL	Recessed	3L-F48-T8-25w	1	66	New Fixture	2x4 LED Hinge Panel 30w	1	30
109	OFFICE 250M	FL	Recessed	3L-F48-T8-25w	4	66	New Fixture	2x4 LED Hinge Panel 30w	4	30
110	MAIN HALL	FL	Recessed	3L-F48-T8-25w	14	66	New Fixture	2x4 LED Hinge Panel 30w	14	30

Table 2 continued on next page

Table 2 Continued

111	Family RR	FL	Recessed	3L-F48-T8-25w	1	66	New Fixture	2x4 LED Hinge Panel 30w	1	30
112	MENS RR	FL	Recessed	3L-F48-T8-25w	1	66	New Fixture	2x4 LED Hinge Panel 30w	1	30
113	CONF ROOM	FL	Recessed	3L-F48-T8-25w	18	66	New Fixture	2x4 LED Hinge Panel 30w	18	30
114	WOMEN RR	FL	Recessed	3L-F48-T8-25w	1	66	New Fixture	2x4 LED Hinge Panel 30w	1	30
115	250H KITCHEN	FL	Recessed	3L-F48-T8-25w	2	66	New Fixture	2x4 LED Hinge Panel 30w	2	30
116	250G MECH	FL	[INTERIOR]	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED	1	21
117	OFFICE 250Q	FL	Recessed	3L-F48-T8-25w	8	66	New Fixture	2x4 LED Hinge Panel 30w	8	30
118	OFFICE 250F	FL	Recessed	3L-F48-T8-25w	3	66	New Fixture	2x4 LED Hinge Panel 30w	3	30
119	ELEC 250E	FL	[INTERIOR]	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
120	OFFICE 250A	FL	Recessed	3L-F48-T8-25w	4	66	New Fixture	2x4 LED Hinge Panel 30w	4	30
121	OFFICE STORAGE 250B	FL	Recessed	3L-F48-T8-25w	8	66	New Fixture	2x4 LED Hinge Panel 30w	8	30
122	IT SERVER	FL	Recessed	3L-F48-T8-25w	8	66	New Fixture	2x4 LED Hinge Panel 30w	8	30
123	250D JAN CLOSET	FL	[INTERIOR]	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED	1	21
124	STORAGE PS-01	Inc	[INTERIOR]	100w inc Screw in-relamp only	7	100	Retrofit	1L-15w LED Screw in A19	7	15
125	STORAGE PS-02	FL	[INTERIOR]	2L-F48-T8-25w	6	44	Retrofit	2L-F48-T8-10.5w LED	6	21
126	BOYS LOCKER ROOM 253	FL	[INTERIOR]	2L-F48-T8-25w	11	44	Retrofit	2L-F48-T8-10.5w LED	11	21
127	PE TEACHER OFFICE	FL	[INTERIOR]	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
127	PE TEACHER OFFICE	Inc	[INTERIOR]	100w inc Screw in-relamp only	2	100	Retrofit	1L-15w LED Screw in A19	2	15
128	DOOR 27 HALLWAY	FL	Surface	1L-F48-T8-25w	6	22	Remove	Demo Existing Fixture	6	0
128	DOOR 27 HALLWAY	LED	Recessed	New 2x2 30w LED Flat Panel	3	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	3	30
129	RR IN CR255	FL	[INTERIOR]	2L-F48-T8-25w	3	44	Retrofit	2L-F48-T8-10.5w LED	3	21
130	HALLWAY OUTSIDE CR255	FL	Surface	1L-F48-T8-25w	20	22	New Fixture	20w 4' LED SM Strip	20	20
131	256 -WORKOUT ROOM	FL	[INTERIOR]	2L-F48-T8-25w	12	44	Retrofit	2L-F48-T8-10.5w LED	12	21
132	256E STORAGE	Inc	[INTERIOR]	100w inc Screw in-relamp only	5	100	Retrofit	1L-15w LED Screw in A19	5	15
133	OFFICE	FL	[INTERIOR]	4L-F48-T8-25w	2	85	Retrofit	4L-F48-T8-10.5w LED	2	42
134	HALLWAY	FL	Surface	2L-F24-T8U-25w	3	44	New Fixture	2x2 LED Hinge Panel 20w	3	20
135	MAIN GYM HALLWAY	FL	Surface	4L-F48-T8-25w	17	85	New Fixture	2x4 LED Hinge Panel 30w	17	30
135	MAIN GYM HALLWAY	FL	Recessed	2L-F48-T8-25w	8	44	New Fixture	1x4 LED Hinge Panel 20w	8	20
136	TROPHE CASE	FL	[INTERIOR]	2L-F48-T8-25w	6	44	Retrofit	2L-F48-T8-10.5w LED	6	21
137	JAN CLOSET	Inc	[INTERIOR]	100w inc Screw in-relamp only	2	100	Retrofit	1L-15w LED Screw in A19	2	15
138	CONCESION STAND #1	FL	Recessed	2L-F48-T8-25w	2	44	New Fixture	1x4 LED Hinge Panel 20w	2	20
139	CONCESION STAND #2	FL	Recessed	2L-F48-T8-25w	2	44	New Fixture	1x4 LED Hinge Panel 20w	2	20
140	VENDING MACHINE	FL	Recessed	2L-F48-T8-25w	2	44	New Fixture	1x4 LED Hinge Panel 20w	2	20
141	MAIN LIBRARY HALLWAY	FL	Recessed	2L-F24-T8U-25w	23	44	New Fixture	2x2 LED Hinge Panel 20w	23	20
142	200L -IT CLOSET	FL	Recessed	4L-F48-T8-25w	1	85	New Fixture	2x4 LED Hinge Panel 30w	1	30
143	LIBRARY (HIGHER CEILING AREA)	FL	Surface	2L-F48-T8-25w	66	44	Remove	Demo Existing Fixture	66	0
143	LIBRARY (HIGHER CEILING AREA)	LED	Recessed	New 2x2 30w LED Flat Panel	30	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	30	30
144	OFFICE 238A	FL	Surface	2L-F48-T8-25w	4	44	Remove	Demo Existing Fixture	4	0
144	OFFICE 238A	LED	Recessed	New 2x2 30w LED Flat Panel	2	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	2	30
145	RECEPTION AREA	FL	Surface	2L-F48-T8-25w	6	44	Remove	Demo Existing Fixture	6	0
145	RECEPTION AREA	LED	Recessed	New 2x2 30w LED Flat Panel	3	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	3	30
146	LIBRARY (LOWER CEILING AREA)	FL	Recessed	2L-F24-T8U-25w	6	44	New Fixture	2x2 LED Hinge Panel 20w	6	20
146	LIBRARY (LOWER CEILING AREA)	FL	Surface	2L-F48-T8-25w	21	44	Remove	Demo Existing Fixture	21	0
146	LIBRARY (LOWER CEILING AREA)	LED	Recessed	New 2x2 30w LED Flat Panel	11	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	11	30
147	CONF ROOM 239	FL	Surface	2L-F48-T8-25w	14	44	Remove	Demo Existing Fixture	14	0
147	CONF ROOM 239	LED	Recessed	New 2x2 30w LED Flat Panel	8	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	8	30
148	FACULTY WORK 237	FL	Surface	4L-F48-T8-25w	1	85	New Fixture	2x4 LED Hinge Panel 30w	1	30
148	FACULTY WORK 237	FL	Surface	4L-F48-T8-25w	6	85	Retrofit	4L-F48-T8-10.5w LED	6	42
149	FACULTY KITCHEN	FL	[INTERIOR]	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED	1	21
150	230 BOYS RR	FL	Surface	2L-F24-T8U-25w	3	44	New Fixture	2x2 LED Hinge Panel 20w	3	20

Table 2 continued on next page

Table 2 Continued

151	232 GIRLS RR	FL	Surface	2L-F24-T8U-25w	3	44	New Fixture	2x2 LED Hinge Panel 20w	3	20
152	DOOR 29 HALLWAY	FL	Surface	1L-F48-T8-25w	36	22	Remove	Demo Existing Fixture	36	0
152	DOOR 29 HALLWAY	LED	Recessed	New 2x2 30w LED Flat Panel	12	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	12	30
153	CR # 229 HOME ED	FL	Surface	2L-F48-T8-25w	16	44	Remove	Demo Existing Fixture	16	0
153	CR # 229 HOME ED	LED	Recessed	New 2x2 30w LED Flat Panel	6	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	6	30
154	CR # 228	FL	Surface	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
154	CR # 228	LED	Recessed	New 2x2 30w LED Flat Panel	9	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	9	30
155	CR # 227	FL	Surface	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
155	CR # 227	LED	Recessed	New 2x2 30w LED Flat Panel	9	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	9	30
156	CR # 223	FL	Surface	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
156	CR # 223	LED	Recessed	New 2x2 30w LED Flat Panel	9	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	9	30
157	CR # 222	FL	Surface	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
157	CR # 222	LED	Recessed	New 2x2 30w LED Flat Panel	9	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	9	30
158	CR # 221	FL	Surface	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
158	CR # 221	LED	Recessed	New 2x2 30w LED Flat Panel	9	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	9	30
159	CR # 224	FL	Surface	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
159	CR # 224	LED	Recessed	New 2x2 30w LED Flat Panel	9	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	9	30
160	DOOR 30 HALLWAY	FL	Surface	1L-F48-T8-25w	23	22	Remove	Demo Existing Fixture	23	0
160	DOOR 30 HALLWAY	LED	Recessed	New 2x2 30w LED Flat Panel	7	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	7	30
161	ART ROOM CR # 226	CFL	[INTERIOR]	1L-26w CFL screw in A19	2	26	Retrofit	1L-15w LED screw in	2	15
161	ART ROOM CR # 226	FL	Recessed	2L-F48-T8-25w	2	44	New Fixture	1x4 LED Hinge Panel 20w	2	20
161	ART ROOM CR # 226	FL	Surface	2L-F48-T8-25w	30	44	Remove	Demo Existing Fixture	30	0
161	ART ROOM CR # 226	LED	Recessed	New 2x2 30w LED Flat Panel	15	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	15	30
162	ART ROOM CR # 225	CFL	[INTERIOR]	1L-26w CFL screw in A19	2	26	Retrofit	1L-15w LED screw in	2	15
162	ART ROOM CR # 225	FL	Recessed	2L-F48-T8-25w	2	44	New Fixture	1x4 LED Hinge Panel 20w	2	20
162	ART ROOM CR # 225	FL	Surface	2L-F48-T8-25w	26	44	Remove	Demo Existing Fixture	26	0
162	ART ROOM CR # 225	LED	Recessed	New 2x2 30w LED Flat Panel	12	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	12	30
163	MECH ROOM HALLWAY	FL	[INTERIOR]	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED	1	21
164	AHU ROOM	FL	[INTERIOR]	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED	1	21
165	BOILER ROOM#3	FL	Suspended	2L-F48-T8-25w	5	44	Retrofit	2L-F48-T8-10.5w LED	5	21
166	2ND FLOOR STAIRS	FL	Surface	2L-F24-T8U-25w	1	44	New Fixture	2x2 LED Hinge Panel 20w	1	20
167	JAN CLOSET @STAIRS	Inc	[INTERIOR]	100w inc Screw in-relamp only	1	100	Retrofit	1L-15w LED Screw in A19	1	15
168	GIRLS LOCKER ROOM	FL	[INTERIOR]	2L-F48-T8-25w	14	44	Retrofit	2L-F48-T8-10.5w LED	14	21
169	PE OFFICE	FL	[INTERIOR]	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
169	PE OFFICE	Inc	[INTERIOR]	100w inc Screw in-relamp only	1	100	Retrofit	1L-15w LED Screw in A19	1	15
170	PE OFFICE #2	FL	[INTERIOR]	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
171	SHOWER	Inc	[INTERIOR]	100w inc Screw in-relamp only	1	100	Retrofit	1L-15w LED Screw in A19	1	15
171	SHOWER	Inc	[INTERIOR]	100w inc Screw in-relamp only	1	100	Retrofit	1L-15w LED Screw in A19	1	15
172	OPEN SHOWER	FL	[INTERIOR]	2L-F48-T8-25w	3	44	Retrofit	2L-F48-T8-10.5w LED	3	21
173	BOYS LOCKER ROOM	FL	[INTERIOR]	2L-F48-T8-25w	13	44	Retrofit	2L-F48-T8-10.5w LED	13	21
174	TEACHER PE	FL	[INTERIOR]	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
174	TEACHER PE	Inc	[INTERIOR]	100w inc Screw in-relamp only	3	100	Retrofit	1L-15w LED Screw in A19	3	15
175	STORAGE @STAIRS	CFL	[INTERIOR]	1L-26w CFL screw in A19	1	26	Retrofit	1L-15w LED screw in	1	15
176	SHOWER AREA	Inc	[INTERIOR]	100w inc Screw in-relamp only	2	100	Retrofit	1L-15w LED Screw in A19	2	15
177	STORAGE	CFL	[INTERIOR]	1L-26w CFL screw in A19	1	26	Retrofit	1L-15w LED screw in	1	15
178	LIBRARY OFFICE 240	FL	Surface	2L-F48-T8-25w	2	44	New Fixture	20w 4' LED SM Strip	2	20
179	LIBRARY SMALL HALLWAY	FL	Surface	1L-F48-T8-25w	1	22	New Fixture	20w 4' LED SM Strip	1	20
180	242 CONF ROOM	FL	Recessed	3L-F48-T8-25w	6	66	New Fixture	2x4 LED Hinge Panel 30w	6	30

Table 2 continued on next page

Table 2 Continued

181	241 STORAGE	FL	Surface	2L-F48-T8-25w	3	44	New Fixture	20w 4' LED SM Strip	3	20
181	241 STORAGE	FL	[INTERIOR]	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
182	BOOK STORAGE	FL	[INTERIOR]	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
183	STORAGE NEXT TO BOOK STORAGE	FL	[INTERIOR]	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
184	CR#201	FL	Recessed	4L-F48-T8-25w	11	85	New Fixture	2x4 LED Hinge Panel 30w	11	30
185	WOMEN FACULTY LOUNGE	CFL	[INTERIOR]	1L-26w CFL screw in A19	2	26	Retrofit	1L-15w LED screw in	2	15
185	WOMEN FACULTY LOUNGE	FL	Surface	2L-F24-T8U-25w	1	44	New Fixture	2x2 LED Hinge Panel 20w	1	20
186	MENS FACULTY RR	CFL	[INTERIOR]	1L-26w CFL screw in A19	2	26	Retrofit	1L-15w LED screw in	2	15
187	200- TEACHER OFFICE	FL	Surface	2L-F48-T8-25w	6	44	New Fixture	20w 4' LED SM Strip	6	20
188	201A GIRLS RR	FL	Surface	2L-F24-T8U-25w	3	44	New Fixture	2x2 LED Hinge Panel 20w	3	20
189	201C -BOYS RR	FL	Surface	2L-F24-T8U-25w	3	44	New Fixture	2x2 LED Hinge Panel 20w	3	20
190	HALLWAY LOCKER ROOM SECTION	FL	Surface	2L-F24-T8U-25w (6" Wide)	7	44	Retrofit	2L-F24-T8U-15w LED 6" Bend	7	30
191	OFFICE 200A	FL	Surface	2L-F48-T8-25w	2	44	New Fixture	20w 4' LED SM Strip	2	20
192	OFFICE 200C	FL	Surface	2L-F48-T8-25w	2	44	New Fixture	20w 4' LED SM Strip	2	20
193	OFFICE 200B	FL	Surface	2L-F48-T8-25w	2	44	New Fixture	20w 4' LED SM Strip	2	20
194	2ND FLOOR HALLWAY	FL	Recessed	2L-F24-T8U-25w	6	44	New Fixture	2x2 LED Hinge Panel 20w	6	20
194	2ND FLOOR HALLWAY	FL	Surface	2L-F24-T8U-25w	3	44	New Fixture	2x2 LED Hinge Panel 20w	3	20
194	2ND FLOOR HALLWAY	CFL	[INTERIOR]	6" Can 26w CFL screw in	6	26	New Fixture	6" LED Can Retrofit 12w	6	12
195	OFFICE 302	FL	Recessed	4L-F48-T8-25w	4	85	New Fixture	2x4 LED Hinge Panel 30w	4	30
195	OFFICE 302	Inc	[INTERIOR]	100w inc Screw in-relamp only	2	100	Retrofit	1L-15w LED Screw in A19	2	15
196	CR #304	FL	Recessed	4L-F48-T8-25w	11	85	New Fixture	2x4 LED Hinge Panel 30w	11	30
197	CR#301	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
197	CR#301	FL	Suspended	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
198	CR#303	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
198	CR#303	FL	Suspended	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
199	ELEC CLOSET	CFL	[INTERIOR]	1L-26w CFL screw in A19	1	26	Retrofit	1L-15w LED screw in	1	15
200	CR#305	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
200	CR#305	FL	Suspended	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
201	CR#306	LED	Recessed	New 2x4 40w LED Flat Panel	12	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	12	40
201	CR#306	FL	Suspended	2L-F48-T8-25w	32	44	Remove	Demo Existing Fixture	32	0
202	306B STORAGE	FL	Suspended	2L-F48-T8-25w	5	44	Retrofit	2L-F48-T8-10.5w LED	5	21
203	306A OFFICE	FL	Suspended	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
204	CR#307	FL	Recessed	2L-F48-T8-25w	9	44	New Fixture	2x4 LED Hinge Panel 30w	9	30
205	DOOR 35 HALLWAY	FL	Surface	2L-F24-T8U-25w	6	44	New Fixture	2x2 LED Hinge Panel 20w	6	20
205	DOOR 35 HALLWAY	CFL	[INTERIOR]	6" Can 26w CFL screw in	10	26	New Fixture	6" LED Can Retrofit 12w	10	12
206	CR #107	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
206	CR #107	FL	Suspended	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
207	CR#108	FL	Recessed	4L-F48-T8-25w	10	85	New Fixture	2x4 LED Hinge Panel 30w	10	30
208	CR#106	FL	Recessed	4L-F48-T8-25w	10	85	New Fixture	2x4 LED Hinge Panel 30w	10	30
209	CR#105	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
209	CR#105	FL	Suspended	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
210	CR#104	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
210	CR#104	FL	Suspended	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
211	CR#102	FL	Recessed	4L-F48-T8-25w	8	85	New Fixture	2x4 LED Hinge Panel 30w	8	30
212	CR#101	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
212	CR#101	FL	Suspended	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
213	CR#103	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
213	CR#103	FL	Suspended	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
214	CR#205	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
214	CR#205	FL	Surface	2L-F48-T8-25w	24	44	Remove	Demo Existing Fixture	24	0
215	DOOR 34 HALLWAY	FL	Surface	4L-F48-T8-25w	5	85	New Fixture	2x4 LED Hinge Panel 30w	5	30

Table 2 continued on next page

Table 2 Continued

216	CR#206	FL	Surface	2L-F48-T8-25w	20	44	Remove		Demo Existing Fixture	20	0
216	CR#206	LED	Recessed	New 2x2 30w LED Flat Panel	9	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		9	30
217	CR#207	FL	Surface	2L-F48-T8-25w	20	44	Remove		Demo Existing Fixture	20	0
217	CR#207	LED	Recessed	New 2x2 30w LED Flat Panel	9	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		9	30
218	DOOR 33 HALLWAY	FL	Surface	1L-F48-T8-25w	29	22	Remove		Demo Existing Fixture	29	0
218	DOOR 33 HALLWAY	LED	Recessed	New 2x2 30w LED Flat Panel	10	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		10	30
219	CR#208	FL	Surface	2L-F48-T8-25w	20	44	Remove		Demo Existing Fixture	20	0
219	CR#208	LED	Recessed	New 2x2 30w LED Flat Panel	9	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		9	30
220	CR#210	FL	Surface	2L-F48-T8-25w	34	44	Remove		Demo Existing Fixture	34	0
220	CR#210	LED	Recessed	New 2x2 30w LED Flat Panel	9	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		9	30
221	210A STORAGE	FL	[INTERIOR]	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED		4	21
222	206A STORAGE	FL	[INTERIOR]	2L-F48-T8-25w	8	44	Retrofit	2L-F48-T8-10.5w LED		8	21
223	CR#209	FL	Surface	2L-F48-T8-25w	20	44	Remove		Demo Existing Fixture	20	0
223	CR#209	LED	Recessed	New 2x2 30w LED Flat Panel	9	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		9	30
224	CR#211	FL	Surface	2L-F48-T8-25w	20	44	Remove		Demo Existing Fixture	20	0
224	CR#211	LED	Recessed	New 2x2 30w LED Flat Panel	9	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		9	30
225	211A STAFF RR MEN	FL	Surface	2L-F48-T8-25w	3	44	Retrofit	2L-F48-T8-10.5w LED		3	21
226	214 STORAGE	FL	[INTERIOR]	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED		2	21
227	CR#213	FL	Surface	2L-F48-T8-25w	30	44	Remove		Demo Existing Fixture	30	0
227	CR#213	LED	Recessed	New 2x2 30w LED Flat Panel	12	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		12	30
228	213A LAB	FL	[INTERIOR]	2L-F48-T8-25w	7	44	Retrofit	2L-F48-T8-10.5w LED		7	21
229	ROOM 215 -TEACHER LOUNGE	FL	[INTERIOR]	2L-F48-T8-25w	6	44	Retrofit	2L-F48-T8-10.5w LED		6	21
230	DOOR 32L HALLWAY	CFL	[INTERIOR]	6" Can 26w CFL screw in	2	26	New Fixture	6" LED Can Retrofit 12w		2	12
230	DOOR 32L HALLWAY	FL	Surface	1L-F48-T8-25w	41	22	Remove		Demo Existing Fixture	41	0
230	DOOR 32L HALLWAY	LED	Recessed	New 2x2 30w LED Flat Panel	14	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		14	30
231	CR216	FL	Surface	2L-F48-T8-25w	32	44	Remove		Demo Existing Fixture	32	0
231	CR216	LED	Recessed	New 2x2 30w LED Flat Panel	16	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		16	30
232	216A STORAGE	CFL	[INTERIOR]	1L-26w CFL screw in A19	1	26	Retrofit	1L-15w LED screw in		1	15
233	CR217	FL	Surface	2L-F48-T8-25w	2	44	New Fixture	20w 4' LED SM Strip		2	20
233	CR217	FL	[INTERIOR]	2L-F48-T8-25w	1	44	Retrofit	2L-F48-T8-10.5w LED		1	21
233	CR217	FL	Surface	2L-F48-T8-25w	28	44	Remove		Demo Existing Fixture	28	0
233	CR217	LED	Recessed	New 2x2 30w LED Flat Panel	12	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		12	30
234	217 A STORAGE	FL	[INTERIOR]	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED		4	21
235	CR#218	FL	Surface	2L-F48-T8-25w	27	44	Remove		Demo Existing Fixture	27	0
235	CR#218	LED	Recessed	New 2x2 30w LED Flat Panel	15	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		15	30
236	218 A STORAGE	Inc	[INTERIOR]	100w inc Screw in-relamp only	1	100	Retrofit	1L-15w LED Screw in A19		1	15
237	CR219	FL	Surface	1L-F48-T8-25w	35	22	Remove		Demo Existing Fixture	35	0
237	CR219	LED	Recessed	New 2x2 30w LED Flat Panel	15	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		15	30
238	CR220	FL	Surface	2L-F48-T8-25w	18	44	Remove		Demo Existing Fixture	18	0
238	CR220	LED	Recessed	New 2x2 30w LED Flat Panel	12	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout		12	30
239	HALLWAY OUTSIDE CR #203	FL	Recessed	2L-F24-T8U-25w	7	44	New Fixture	2x2 LED Hinge Panel 20w		7	20
240	CR204	FL	Surface	2L-F48-T8-25w	38	44	Remove		Demo Existing Fixture	38	0

Table 2 continued on next page

Table 2 Continued

240	CR204	LED	Suspended	New 40w LED Suspended 8' Strip Fixture	15	0	New Fixture	New 40w 8' LED Chain Hung Strip w/ Light Model Layout	15	40
241	204B STORAGE	FL	[INTERIOR]	2L-F48-T8-25w	2	44	Retrofit	2L-F48-T8-10.5w LED	2	21
242	204C	FL	[INTERIOR]	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
243	206A	FL	[INTERIOR]	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
244	CR203	FL	Surface	2L-F48-T8-25w	38	44	Remove	Demo Existing Fixture	38	0
244	CR203	LED	Suspended	New 40w LED Suspended 8' Strip Fixture	15	0	New Fixture	New 40w 8' LED Chain Hung Strip w/ Light Model Layout	15	40
245	203A -STORAGE	CFL	[INTERIOR]	1L-26w CFL screw in A19	1	26	Retrofit	1L-15w LED screw in	1	15
245	203A -STORAGE	FL	[INTERIOR]	2L-F48-T8-25w	7	44	Retrofit	2L-F48-T8-10.5w LED	7	21
246	CR202	LED	Recessed	New 2x4 40w LED Flat Panel	9	0	New Fixture	New 2x4 40w LED Flat Panel w/ Light Model Layout	9	40
246	CR202	FL	Surface	2L-F48-T8-25w	18	44	Remove	Demo Existing Fixture	18	0
247	MISSED ROOMS IN TLC	FL	Recessed	3L-F48-T8-25w	2	66	New Fixture	2x4 LED Hinge Panel 30w	2	30
247	MISSED ROOMS IN TLC	FL	[INTERIOR]	2L-F48-T8-25w	4	44	Retrofit	2L-F48-T8-10.5w LED	4	21
248	DOOR 7 HALLWAY	FL	Recessed	2L-F48-T8-25w	6	44	New Fixture	2x4 LED Hinge Panel 30w	6	30
249	CR 212	FL	Surface	2L-F48-T8-25w	20	44	Remove	Demo Existing Fixture	20	0
249	CR 212	LED	Recessed	New 2x2 30w LED Flat Panel	9	0	New Fixture	New 2x2 30w LED Flat Panel w/ Light Model Layout	9	30
End	End	End	End	End	End	End	End	End	End	End

End of table