

02-16-2026

Board of Trustee
Wednesday 18, 2026

Fire Alarm System upgrade in the PRLHS

The Replacement of the fire alarm system project at PRLHS will include full system replacement to include the addition of an automated voice system, per fire code compliance obligations. The system also includes automatic fire alarm monitoring connected to the fire department central monitoring system to ensure that emergency services are dispatched quickly and automatically in a fire emergency.

Please see attached system list.

The upgrade will start during the District spring break week, March 30, 2026 through April 3, 2026.

Total Cost quoted \$190,099.00.

Thank You

Charity Hinshaw
Facilities Coordinator/Transportation Director

Bill of Materials: Fire alarm system replacement budget pricing

Qty	Manufacturer	Part Number	Description	NOTE: BP = Bulk Pack of 10 devices
Fire Alarm Panel Components				
1	Notifier	CA-1	CHASSIS, DVC, ONE ROW	
1	Notifier	CMIC-1	CHASSIS WITH PAGING MICROPHONE WITH WELL; USED WITH CA-1	
1	Notifier	DAA2-7525	DIGITAL AMPLIFIER 75W, 25V, 120 VAC	
1	Notifier	DPA-1	DRESS PLATE, DVC, ONE ROW	
1	Notifier	DVC-EM	DIGITAL VOICE COMMAND, EXTENDED MEMORY	
1	Notifier	DVC-KD	DIGITAL VOICE COMMAND, KEYPAD	
2	Notifier	BMP-1	BLANK MODULE DRESS PLATE; USED TO COVER ANNUNCIATOR POSITIONS. ALSO MOUNTS SOME OPTION MODULES.	
1	Notifier	BP2-4	BATTERY DRESS PANEL FOR CAB-4 SERIES; FOR USE WITH THE NFS2-3030, NFS2-640, NCA-2, AND DVC SYSTEMS.	
1	Notifier	CHS-4L	CHASSIS, LOW PROFILE, FOR MOUNTING THE AA-30, LDM. (ONLY NFS-3030/NFS-640)	
1	Notifier	CHS-M3	MOUNTING CHASSIS, USED FOR CPU-3030, CPU2-3030, AND NCA-2.	
2	Notifier	DP-1B	DRESS PANEL BLANK; COVERS UNUSED CABINET ROW(S), PAINTED BLACK. (ONLY NFS-3030/NFS-640)	
1	Notifier	DP-DISP	DRESS PLATE, DISPLAY, BLACK. (ONLY NFS-3030/NFS-640)	
1	Notifier	DR-D4	DOOR, LOCK & KEYS. ACCEPTS 4 CHASSIS, BLACK.	
1	Notifier	SBB-D4	BACKBOX, 4 CHASSIS, BLACK.	
1	Notifier	3030-CLSS-KIT-GW	CPU2-3030D + CLSS Gateway	
1	Notifier	ACM-24AT	ONYX SERIES ACS ANNUNCIATOR;	
1	Notifier	LCM-320	LOOP CONTROL MODULE. EACH LCM MAY BE EXPANDED TO TWO LOOPS BY ADDING A LEM-320. NFS2-3030 AND NFS-3030 ONLY.	
1	Notifier	AMPS-24	ADDRESSABLE POWER SUPPLY, 120 VAC (NFS-3030/NFS2-3030).	
1	Notifier	NFS-LBB	NFS LARGE BATTERY BACKBOX, HOUSES UP TO TWO 55 AH BATTERIES, BLACK.	
2	Interstate	SLA1165	SLA1165 IB 12V 55ah SLA FLAG	
1	SpaceAge	E120V-GT	SAE VECP-25 Hybrid Surge Protection Device	
1	Space Age	SAE SSU00672 FDB	Fire Alarm Document Cabinet	
Field Devices				
8	Notifier	SPSCWLED	SPEAKER STROBE LED WHITE CEILING	
10	Notifier	SPSCWLED-BP10	SPEAKER STROBE LED WHITE CEILING BULK PACK W/10	
1	Notifier	SPSWLED-BP10	SPEAKER STROBE LED WHITE WALL BULK PACK W/10	
4	Notifier	SPSRKLED	SPKR/STRB LED RED WALL OUTDOOR	
6	Notifier	DNR	INNOVAIRFLEX INTELLIGENT DUCT DETECTOR, NON-RELAY, DOES NOT INCLUDE HEAD.	
6	Notifier	DST5	INNOVAIRFLEX SAMPLING TUBE, STEEL, 5' WITH HOLES	
3	Notifier	FCM-1	ADDRESSABLE CONTROL MODULE WITH FLASHSCAN; CONFIGURED FOR ONE CLASS A OR CLASS B NAC.	
1	Notifier	FDM-1	ADDRESSABLE DUAL MONITOR MODULE; WITH FLASHSCAN, TWO CLASS B CIRCUITS.	
6	Notifier	FRM-1	ADDRESSABLE RELAY MODULE WITH FLASHSCAN; PROVIDES TWO FORM-C DRY CONTACTS	
6	Notifier	RTS151KEY	REMOTE TEST STATION; WITH SWITCH, ALARM AND POWER LED'S, KEY RESET.	
6	Notifier	FSP-951	INTELLIGENT ADDRESSABLE PHOTO DETECTOR; WITH FLASHSCAN; WHITE	
12	Notifier	FSP-951-BP	INTELLIGENT ADDRESSABLE PHOTO DETECTOR; WITH FLASHSCAN; WHITE BULK PACK 10	
6	Notifier	FSP-951R	REMOTE TEST CAPABLE INTELLIGENT PHOTO DETECTOR WITH FLASHSCAN; FOR USE WITH	
14	Notifier	B300-6-BP	INTELLIGENT FLANGED MOUNTING BASE; 6" INCH; PACK OF 10; WHITE	
1	Notifier	FST-951-BP	INTELLIGENT ADDRESSABLE 135 DEGREE THERMAL DETECTOR WITH FLASHSCAN; WHITE	
4	Notifier	FM996-L8	FM-996, 12 VDC, 24 VAC/VDC, 120/250 VAC, SURFACE WALL MOUNT.	
9	Notifier	STI9708	WIRE GUARD, WHITE, SPECTRALERT ADVANCE ® WALL MOUNT AVS	
2	Notifier	OSE-SPW	EMITTER - STANDARD POWER, WIRED AT 24V DC. SAME AS PART NO OSE-SPW-L8.	
2	Notifier	OSI-90	IMAGER - 80° COVERAGE, 24V DC. SAME AS PART NO OSI-90-L8.	
4	Notifier	OSID-WG	WIRE GUARD	
3	Potter	PSN-106	PSN Series 10A Conventional Power Supply with Outputs, Red Enclosure	
6	Interstate	SLA1075	SLA1075 IB 12V 8ah SLA 187	
3	SpaceAge	E120V-GT	SAE VECP-25 Hybrid Surge Protection Device	
1			Wire, backboxes, etc	

Detailed Statement of Work**SUMMARY**

This is a turnkey proposal for installing a complete new voice evacuation fire alarm system, with smoke/heat detection throughout the school, a manual pull station in the office, and central station monitoring. Includes demo of existing devices.

INCLUSIONS:

- Permit drawings
- Material pre-paid freight and handling to job site
- Warranty on material provided
- Complete submittal package to Authority Having Jurisdiction
- Fire Alarm System permit
- Testing/certification with local fire official
- Electronic submittals/O&M's
- Device trim/installation
- System cable/installation
- Interior conduit – cable to be run open air where code allows
- Device boxes

EXCLUSIONS:

- Patch and paint
- Any additional devices required during plan review or inspection
- State Sales Tax

PROPOSAL NOTES:

1. We will require Auto CAD electronic files provided to us in order to prepare shop drawings.
2. Allow three weeks for preparation of submittals and an additional week to obtain the fire alarm system permit.
3. Proposal based upon work hours of 7:00 AM to 3:30 PM, Monday through Friday.
4. Any additional devices required during plan review and inspections are excluded.
5. Any changes required by deferred submittals may change scope and cost of proposed fire alarm system.
6. Fire alarm equipment will be ordered when we have submittal approval and the fire alarm permit. We will invoice for the equipment when it ships from the factory and receive the factory invoice.

Schedule of Values:

STARTUP/SUBMITTALS/PERMIT - 30%
MATERIAL, INSTALLATION, PROGRAMMING - 90%
FINAL INSPECTION/O&M's, RECORD DRAWINGS - 100%