

All School Sites
NCSD Window Film Project (PWP-NY-2024-183)
Meeting

Nye County School District
Board of Trustees Regular

September 19, 2024

Nate Cardinal, Project Manager of MOSS

Goal:

This project will install 11mm security window film with a bead of silicone structural sealant to all windows under 6' at NDO, SDO, Coalition, MOSS, B Building Warehouse, Northern Transportation, and Southern Transportation.

Discussion:

Initially, the original funding was designated only for sites occupied by students. However, we've now received approval to extend the use of this funding to all sites. As a result, we are seeking approval to add security window film at the following locations: NDO, SDO, Coalition, MOSS, B Building Warehouse, Northern Transportation, and Southern Transportation.

The security window film installation is nearly complete at all school sites, and Security Assessment Group LLC has confirmed they can finish the additional buildings before the grant deadline.

The security film is designed to enhance the safety of our current glass. The film will improve safety by helping protect against break-ins, vandalism, and other threats. The installation of structural sealant (Dow 995) will be applied to the inside to bond the security window film to the window frame. If there is a need for evacuation, this will allow for the window to be removed from the inside for egress. This film is not to be confused with bulletproof glass. The 11mm security film is designed to extend the time needed for an intruder to gain entrance to the school. This will not only allow extra time for staff and students to get to safety but also allow emergency services time to respond.

Warranty:

The contractor we are recommending offers a 10-year warranty on material and a 2-year warranty on labor.

Change Order Cost:

1. Security Assessment Group LLC \$106,786.49

Recommendation:

We recommend approval of Security Assessment Group LLC to complete the job. The total project cost is \$106,786.49

Schedule/Completion Date:

This job is scheduled to start on September 20th, 2024, and will be completed no later than June 30th, 2025. We will work closely with the contractor to work around school schedules and activities to ensure we do not disrupt the academic day as the contractor works district-wide to complete the installation.

Attachments:

Security Assessment Group LLC contract