



133 Sayton Rd. Fox Lake IL, 60020
PH. 847.587.9800 Fax 847.587.4600

October 10, 2013

Job Address:
Gavin South School

- Remove tree, bushes, timbers and plants from 2 landscaped beds, relocate boulders. Excavate and remove approximately 10 inches of soil from beds.
\$600.00
- Install 4 inches of compacted gravel base and 5 inches of 4000psi concrete finish to bed areas.
\$2,800.00
- Install (3) 6" concrete filled steel bollards at approximately 6 foot spacing in new concrete area. Cover with plastic slip covers.
\$2,100.00

Total: \$5,500.00

o