



Mechanical Quote

Ref: Work order # _____

SUBMITTED TO: Craig School District
ATTN: Daniel Nelson – Maintenance Director
EMAIL: dnelson@craigschools.com
PROJECT: Gym Boilers replacement
DATE: Monday, August 21, 2023

Schmolck Mechanical Contractors is submitting a quote for the work on the above noted project for your review and acceptance. Please take this time to review our intended scope of work. Please be advised, Schmolck Mechanical issues monthly progress billings for all projects not completed in the same month started. Please call if you have any questions regarding this policy.

Included in our scope of work:

- Installation of OWNER SUPPLIED Weil McLain WGO-7
 - Set boiler on concrete block pile (in leu of concrete housekeeping pads).
 - Piping connections to existing HWS (boiler side of existing valve).
 - Piping connections to existing HWR (boiler side of existing valve).
 - Fuel connections to existing piping systems including.
 - New General 2A Filter housing complete.
 - New Tiger loop de-aerator.
 - Capping of existing return line in boiler room.
 - New single wall 24-gauge flue connection between boiler and existing chimney.
 - Electrical connections to existing disconnect, and safeties (LWCO).
 - Basic controls connection (boiler enable) from existing control system.
- Setup of OWNER SUPPLIED burner (assuming supplied with Beckett burner).
- Startup and commissioning of installed boiler.
 - Includes combustion analysis test for proper operation.
- Travel, Housing and Per diem costs.

Excluded from our scope of work:

- All work not specifically noted above.
- Demolition and disposal of the existing boilers and burners.
- Circulation pumps, or hydronic accessories (this is a boiler change out only).
- All work related to existing BAS systems if present.
- Repairs or modifications to the existing chimney system.
- Supply of Boiler, Burner or operating controls package. (Owner supplied, delivered to boiler room).
- All concrete work or housekeeping pads.
- Costs associated with any permits if required.
- Balancing of hydronic flows through boiler (see optional adder below).
- Engineering work related to this installation.
- Glycol if this system still includes glycol (owner to provide) and or Flushing of hydronic system piping.
- Mechanical insulation of new work or repairs to existing.



- We will only commit to a schedule for this work once approval has been given.

We offer a lump sum quoted price of \$ 21,500.00 for the scope of work defined above.

❖ **Optional adder for balancing hydronic flows through boiler** **\$6,200.00**

Submitted by _____ **Accepted by** _____
David W. Trudeau Signature
Vice President
Schmolck Mechanical Contractors Inc.
Ketchikan Office

Printed Name Date

The above quote is valid for 1 month. If notification in writing is not submitted to our office within the required amount of time this quote may be voided at the discretion of Schmolck Mechanical Contractors. We look forward to working with you & appreciate your business.

**** Travel notice ** - If weather delays arise on remote projects, there will be an additional charge of \$80/hr for standby time (our pricing includes travel costs and time, but nothing has been budgeted for weather delays). Should weather delays impact our travel plans we will notify you IMMEDIATELY of the additional charges.**