

PROPOSAL

147



BEWLEY ELECTRIC
707A N. Chestnut St.
McKINNEY, TEXAS 75069

(972) 548-9111

TO: Celina ISD
Attn: Donnie
Celina TX 75009

PHONE	DATE
972-948-1061	8/1/2012
JOB NAME / LOCATION	
Old Football Field Celina, TX 75009	
JOB NUMBER	JOB PHONE

We hereby submit specifications and estimates for:

Customer to furnish all material needed for electric panel upgrade of outside panels for football lights and field house. Lighting contactors to be installed with a switch per pole. Electric contractor to furnish back board for panels and all mounting hardware. Customer will have to call their power provider for disconnect and reconnect of meter. BID DOES NOT INCLUDE POWER COMPANY CHARGES. Need to allow 3 days for completion of work.

Regulated By The Texas Department Of Licensing & Regulation
P.O. Box 12157 Austin, TX 78711 800-803-9202 / 512-463-6599
Website: www.license.state.tx.us/complaints TECL# 17465

WE PROPOSE hereby to furnish material and labor — complete in accordance with the above specifications, for the sum of:
Six Thousand One Hundred Fifty and 00/100 Dollars dollars (\$) 6,150.00).

Payment to be made as follows:
Due Upon Completion

All material is guaranteed to be as specified. All work to be completed in a professional manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado, and other necessary insurance. Our workers are fully covered by Worker's Compensation insurance.

Authorized Signature

Note: This proposal may be withdrawn by us if not accepted within 10 days.

ACCEPTANCE OF PROPOSAL — The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature _____

Date of Acceptance: _____

Signature _____

Donnie Tippie

From: Loyd [loyd@eistx.com]
Sent: Friday, July 27, 2012 2:26 PM
To: Donnie Tippie
Subject: FootBall Field Electrical Distribution

- | | | |
|---|---|-------------------|
| 1 | 400amp 240v 1 phase breaker disconnect rain tight | 16" X 27" X 8" |
| 1 | 400amp 240v Main Lug Panel Board Rain tight
Including breakers: 5 100a/2p
1 60a/2p | 20" X 56" X 6.25" |
| 1 | 200amp 240v Main breaker, 40 circuit rain tight
Including breakers: 3 50a/2p
1 125a/2p
2 100a/2p
3 30a/1p
1 20/1p | 20" X 50" X 6.25" |
| 1 | Lighting Panel
Including: 4 – 100a/3p contactors
4 – keyed switches
1 – 24"x24"x8" raintight enclosure with back panel and locking hasp. | 24"x24"x8" |

Wire, Conduit, fittings

Labor not included.

Total \$6,900.00

Thank You,

Loyd R. Crawford
469-247-5210
loyd@eistx.com

Electrical & Industrial Supply

900 Oil Mill Rd., PO Box 2078, Van Alstyne Texas 75495

469-452-4464

WWW.EISTX.COM

Commercial & Industrial

**Electrical, Electronic, Industrial, Janitorial, Safety
Facility & Machinery**

Maintenance Supplies