



January 9th, 2024

School District 23

Eisenhower Elementary School

1 North Schoenbeck Road,

Prospect Heights, IL 60070

Scope of Work: **\$25,000.00**

PPM will provide all labor, materials, and machinery to install new path section per provided map. Proposed path earth will be excavated, hauled off site and disposed of legally. PPM will install 8" of stone base and compact as required. PPM will install 2" of IDOT binder course asphalt and roll to required compaction. PPM will install 2" of IDOT surface course asphalt and roll to required compaction.

A required allowance of \$5,000.00 for landscaping restoration is not included in this price.

All work to be performed Monday – Friday.

Any work not detailed above will incur an additional charge.

Accepted By: _____