



Burrage Roofing - Chicago

Company Representative
 Jack Molskow
 Phone: (630) 267-3852
 jack@burrageroofing.com

**Retail w/ EDCO Siding
 tax exempt**

02/16/2026
Claim Information

Antwon Blake
 150 N Winfield Road
 Winfield, IL 60190
 (708) 595-1924

Job: Antwon Blake

Roofing Section

	Qty	Unit
Material		
IKO Dynasty AR (3 BD/SQ)	16.33	SQ
IKO Hip and Ridge 12 AR (36')	2.00	BD
IKO Leading Edge Plus Starter (123')	1.42	BD
TopShield TS20 Synthetic Underlayment (10 sq)	1.63	RL
IKO Stormshield Ice & Water (2 sq)	2.20	RL
TopShield Galvanized Steel Roof Edge w/ Hem - 30GA - SR Style - 5" (10')	18.70	PC
TopShield Electro Galvanized Plastic Cap Nails - Ring Shank - 1" (2000 Cnt)	0.91	BX
TopShield Electro Galvanized Steel Roofing Coil Nails - 1 1/4" (7200 Cnt)	0.91	BX
Top Shield Elastomeric Sealant - Plastic Tube (10.1 oz)	2.00	EA
TopShield Aluminum Prebent Step Flashing w/ Crimp - 4"x4"x8" (100 PC/BD)	1.00	BD
Labor		
Install Shingles	17.77	SQ
Additional Layer Shingles Removal	16.00	SQ
Steep Roof 9/12	16.00	SQ
2 Story Roof	16.00	SQ
Flashing (End Wall, Step)	10.00	LF
Haul Off Debris	16.00	EA
General		
Material Tax	1.00	EA
Delivery Charge	1.00	EA
Eagleview	1.00	EA

--

Siding Section

EDCO Steel 12" OC Board and batten siding on gables and short wall adjoining flat roof

	Qty	Unit
EDCO Steel 12" OC Board and Batten w/ accessories	1.00	EA
OSI Quad Sealant (10 oz)	2.00	EA
1/4" fanfold	700.00	SF
TopShield HouseWrap - 9'x100'	770.00	SF
Tyvek Housewrap Tape - 1.88"x164'	70.00	LF

Electro Galvanized Roofing Nails - 2 1/2" (30 lb)	1.00	BX
TopShield Aluminum Painted Trim Coil - .017 - 24"x50' - White/White	1.00	RL
Labor		
Install Siding and underlayments	700.00	EA
Haul Off Debris	1.00	EA
remove battens prep substrate	700.00	EA
Install vertical furring strips for BNB	220.00	LF
General		
Eagleview	1.00	EA
Delivery Charge	1.00	EA

--

Gutters Section

	Qty	Unit
Seamless Gutters 6"	80.00	EA
Downspouts 3x4	40.00	EA

--

Siding Section

Soffit and fascia on gables

	Qty	Unit
ACM Painted Aluminum Trim Coil - 24"x50'	1.00	RL
ACM Norandex Aluminum Solid Soffit - T4	45.50	LF
ACM Aluminum Soffit - Center Vented - T4	19.50	LF
ACM Aluminum Universal F-Channel - 3/8" (12')	65.00	LF
ABC Stainless Steel Trim Nails - 1 1/4" (1 lb)	1.00	BX
Labor		
Soffit Labor	65.00	LF
Fascia Labor	65.00	LF

--

Siding Section

fascia on Eaves with subfascia wood replacement

	Qty	Unit
ACM Painted Aluminum Trim Coil - 24"x50'	1.00	RL
ABC Stainless Steel Trim Nails - 1 1/4" (1 lb)	1.00	BX
Labor		
Fascia Labor	110.00	LF
replace subfascia boards	120.00	EA

--

TOTAL \$34,978.55

Starting at **\$347/month** with  **Acorn** FINANCE • [APPLY](#)

Note:
 plywood replacement 90 per sheet billed additionally as change order where needed.
 By signing this document, the customer agrees to the services and conditions outlined in this

document. Please make all checks payable to Burrage Roofing. Total due in 14 days after completion of work. Overdue accounts subject to a service charge of 10% per month.

.....
.....

Company Authorized Signature

Date

Customer Signature

Date

Customer Signature

Date



Winfield 34 - Where Learning is Personal

•Valuing Connections •Fostering an Inclusive Community •Supporting Student Growth
(Staff - Students - Families)

Request for Quote

DATE: Jan 1st, 2026
QUOTE NAME: primary shingle roofing replacement
PROJECT LEAD: Antoine Blake
CONTACT INFORMATION PHONE & EMAIL: 708-595-1924 Antoine Blake
VENDOR LEAD: burrage roofing
VENDOR CONTACT NAME: Jack Molskow
VENDOR CONTACT PHONE & EMAIL: Cell: 630 267 3852 /jack@burrageroofing.com

Winfield School District 34 requests a quote for the following:

1. Remove existing shingles on the primary roof. Replace any bad plywood underneath, and replace with new shingles.
2. Remove and replace the existing gutter , soffit, and short downspouts on the playground side of bldg.
3. Remove existing wood siding on the north, east, and south sides of the shingle and replace it with metal siding matching existing metal siding on the Winfield rd. side of the bldg.