

Standard Proposal

***JOHNSON FLOOR COMPANY, INC.***

9690 W. 55<sup>th</sup> Street • Countryside, IL 60525 • 708-354-5510 • Fax 708-354-9205

Mr. Jim Caldwell  
Lincolnwood SD 74  
6970 Prairie Ave  
Lincolnwood, IL

Date: September 15<sup>th</sup>, 2022  
Location: Lincoln Hall School  
Classroom  
Operation: Carpet Tile + Reducer

See: Proposal

We agree to furnish labor and material to install new vinyl backed carpet tile at the location stated above. Due to the manufacturing and composition of this carpet tile, it can only be installed with either full spread adhesive or with a peel-n-stick backing. The new carpet tile is to be installed with a solid vinyl reducer at the doorway. Alternates have been included for the installation of the carpet tile with J&J flooring's "Prefix" peel-n-stick system and for vinyl backed carpet tile that can be installed with manufacturer recommended tabs. Exclusions are included and are listed after pricing. All labor is figured at regular working time, with work to be completed by June 1<sup>st</sup>, 2023

**J&J Kinetex Glue Down Hybrid Carpet Tile + Reducer .....\$6266.00**

CPT-1: J&J *Kinetex – Umbra Stripe*, color: 1789 Shadow Stripe, 18" x 36" carpet tile, installed with Kinetex "full-spread" adhesive

The furnishing and installation of new Tarkett *EG-XX-H* solid vinyl reducer at doorways  
\*includes product for 1250 sqft of material

**Alternate for J&J Kinetex, Prefix Peel-N-Stick System add.....\$432.00**

Add for J&J Kinetex *Prefix* peel-n-stick system

**J&J Carpet Tile, Journey 7621 Installed with Tabs .....\$5310.00**

CPT-1: J&J *Journey 7621*, all colors, 18" x 36" carpet tile, installed with J&J "Tabs" for floating installation

**Alternate for Carpet Tile, J&J Fastrack 7578 Installed with Tabs deduct.....\$795.00**

Substitute J&J *Fastrack 7578* 18" x 36" carpet tile for J&J *Journey* 18" x 36" carpet tile

**NOTE:** Payment in full is expected upon satisfactory completion of the work described above unless prior written arrangements have been made.

**FOR TERMS AND CONDITIONS, PLEASE SEE REVERSE SIDE**

**Exclusions**

Any and all work involving sheet vinyl and solid vinyl tile

Any and all work involving moisture testing of the existing concrete

The hauling of materials up stairwells

Any and all work involving custom floor transitions

The protection of the existing flooring

Any and all work involving abatement

The moving of existing furniture/equipment

Any and all work involving wall base

If this proposal is acceptable, please sign one copy and return to our office. Thank you.

Mike Johnson