P: 800.433.0912 | F: 940.549.1365 P.O. Box One | 801 Fifth St. | Graham, TX 76450 www.SouthernBleacher.com Facebook | Twitter | Instagram | LinkedIn

QUOTE

April 9, 2024

Harry C. Lau Administrator Facilities and Operations Livonia Public Schools 15125 Farmington Rd.

RE: Livonia Churchill High School – New Pool Bleachers

Southern Bleacher Company is pleased to offer the following quotation for the above referenced project. Cost includes freight and Installation to: Livonia, MI

- Provide One (1) Pool Bleacher:
- Provide Code Compliant Non-Elevated Angle Frame Bleacher (Silver Edition)
- All Aluminum Understructure
- 8 rows x 69' long
- 8" Rise/24" Treads
- Aisles w/handrails
- Vertical Picket Guard Railings Black or Silver Anodized Aluminum
- Wheelchair Spaces per code
- Anodized Extruded Aluminum Bench Seats.
- Painted Extruded Aluminum Risers (std. colors).
- Mill finish extruded aluminum footboards.

Delivered and Installed onto contractor supplied concrete pad designed to accommodate the bleacher: <u>\$74,845.00</u>

Includes:

- All Aluminum understructure
- Freight
- Sales Tax
- Unloading and Installation by Southern Bleacher (non-union, non-prevailing wages) by Factory Certified Technicians.
- Engineered Drawings stamped by a Professional Engineer in the State of Michigan

Excludes:

- Concrete pad or pathways to and from exit locations flatwork beneath the exit ramp and stairs
- Any state or local, permits, fees, etc.
- Any bonds.
- Seat Numbers
- Allowances
- Onsite restoration
- Any item not listed in above inclusions.

Lead Times:

- Engineer Stamped Shop Drawings 3-4 weeks from Notice to Proceed
- Material Delivery after Returned APPROVED Shop Drawings 60 90 Calendar Days
- Installation 1-2 weeks

NOTE: Southern Bleacher requires adequate site access to perform our work.

The above price is valid for 30 days.

Respectfully submitted,

David Southwell

Field Sales Manager