

1) Replace garage door in weight room (old shop). \$7,067.00

This will replace the existing damaged door with a new insulated door with an opener that has a safety feature. This will also have a lockout and alert if opened.

2) Replace weight room (old shop) exterior man door. \$3,210.51

This will replace the existing damaged door with a steel security door. This will have the built in ability to add a fob reader in the future if we wanted to allow access after hours.

3) Replace the front entry and rear exit doors on Pre-K. \$13,183.80

This will replace the existing wooden entry and exit doors that are in rough shape with steel security doors.

4) Addition of cameras Pre-K, weight room exterior, between HS and Library, HS entrance. \$31,651.00

Currently the Pre-K only has one camera on the inside facing the entrance. This will provide exterior cameras giving us a 360 degree view around the building. Cover both parking areas, the playground, bus pickup/drop off and give us a view of the baseball field. This will also give us a view of the weight room exterior, rear parking lot, baseball field, grass area between the school and library and HS front entrance.

5) Crack fill, seal coat, and restripe from parking lot. \$36,434

The front HS parking lot is due for crack fill and seal coat. This should be done every 3-5 years depending on traffic and deterioration to maintain the parking lot.

6) Replace Pre-k Climber and add shade to GS playground. \$51,920.30

This will replace the damaged Pre-k climber with a new climber, playhouse, interactive bench, and fence touch activity boards. This will also add two 12'x12'x8' shade structures to the GS Playground.

7) Concrete GS playground BB court and replace hoops. Concrete \$88,600. BB Hoops \$11,704

This will remove the cracked and damaged asphalt court and replace it with a longer lasting concrete court. The existing hoops are old, damaged and leaning. This will replace the hoops and poles with brand new Buzzer Beater hoops and poles. (Mr. Gronewald will remove the old Pre-K climber, asphalt basketball court and hoops, this saved \$10,000 off the project.)

8) Completely resurface HS gym and stage. \$43,850

The HS gym and stage finish is in rough shape. This will sand down both the gym floor and stage to bare wood. Apply new stain, base coat, lines, graphics and top coat.

9) Replace batting cage and pitching warm up mounds at baseball field. \$38,115.74

This will remove the old batting cage and pitching mounds at the baseball field and replace them with a 70' x14' x12'H single tunnel batting cage and two elevated clay pitching mounds. Batting cage poles will be 8.625"OD x 19'L x .322 heavy duty wall. Poles will be secured 7' deep with 24" bore and filled with 4,000 psi concrete. Net will be #36 Nylon 1-³/₄" mesh with black rope border. This will include all new snaps, cable, and hardware.

10) Install new window in old HS concession stand \$2,827.76

This will install a new wider concession window in the old HS concession stand. This will move the concession from the cafeteria into the old concession room right outside the HS gym door.