

Pacific Northwest Fence Co.

2-4-26

Winston/Dillard School Dist.
Winston Middle School
330 Thompson Ave.
Winston, OR 97496

Installation of approx. 455' of 6' galvanized chain link wire fence.

Installation of one single swing walk gates with panic bar..

Panic bar gates will have 4" x 4" square galvanized posts with 1 1/2" diameter pipe header.
Gate height to be 6' tall.

Materials

1. 9 gauge commercial weight chain link wire
2. 1 5/8" diameter top rail 16 gauge tubing
3. 1 1/2" square walk gate frame and header
4. 1 7/8" diameter line post set 10' on center or less apart
5. 2 3/8" diameter terminal post
6. 4" x 4" square gate and latch post (Panic Bar)
7. 9 gauge bottom tension wire
8. All post set in concrete
9. All welded gate construction
10. All posts are schedule 40 commercial weight
11. Lockeye Panic bar
12. 24" Shield
13. Self closing hinges for walk gate with panic bar

A contract with all required State forms will be delivered before start of any work.

Prices include all materials and labor.

Payment to be made upon completion.

Price -----\$15,452.00

Please call with any questions.

Best Regards,

Brett Heselius

John Heselius
P.O. Box 179
Roseburg, Oregon 97470
office: (541)672-0482
fax: (541)464-8671
john@pacificnorthwestfence.com